BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2013-14/OW/WORK_INDENT11529/CALL-1

APPROVED SCHEDULE - B

NO.EE/BTP/BBMP/E-PMT/07/2014-15, Date: 31.10.2014

Improvements and Ashalting to Thindlu old Village in ward No. 09 in Vidyaranyapura sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of C SHIVARAJU	
				In Figures	In Words
1	312.25	Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	95.21	Rupees Ninety Five and Twenty One Paise Only
2	351	Removing B.S. Slab Drain and stacking etc complete as per specifications and directions of engineer in charge of the work	Sqm	52.59	Rupees Fifty Two and Fifty Nine Paise Only
3	351	Refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	73.51	Rupees Seventy Three and Fifty One Paise Only
4	2625	Scarifying stone metal crust 50mm to 100mm thick with pick axes along with premix carpet/surface dressing and stacking of old serviceable materials within a lead of 100 meters by manual means including cost of all labour charges etc complete as per specifications and directions of engineer in charge of the work	Sqm	76.4	Rupees Seventy Six and Forty Paise Only
5	521	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1176.53	Rupees One Thousand One Hundred Seventy Six and Fifty Three Paise Only
6	2655	Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	11.05	Rupees Eleven and Five Paise Only
7	2655	Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means etc complete as per specifications and directions of engineer in charge of the work	Sqm	149.1	Rupees One Hundred Forty Nine and Ten Paise Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

8	66.38	Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. With 80/100 grade bitumen, etc complete as per specifications and directions of engineer in charge of the work	Cum	10475.43	Rupees Ten Thousand Four Hundred Seventy Five and Forty Three Paise Only
9	90	Road marking with hot applied thermoplastic compound with reflect rising glass beads on bituminous surface-providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface to level, uniform and free from streaks and holes etc complete as per specifications and directions of engineer in charge of the work	Sqm	495.27	Rupees Four Hundred Ninety Five and Twenty Seven Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92